## 22.1.4.2 Method Statements

- A. The Contractor shall submit method statements to the Engineer for approval 4 weeks in advance of commencing the site activity in accordance with Section 01300 of the specification. These shall comprise but not necessarily be limited to.
  - i. Procedures for handling, storage and installation of pipes.
  - ii. Hydrostatic testing procedures for uPVC non pressure pipelines..
  - iii. Deflection measurement procedures for uPVC pipelines.

## 22.1.4.3 Drawings

- A. The Contractor shall submit drawings to the Engineer for approval in advance of commencing the site activity in accordance with Section 01300 of the specification. These shall comprise but not necessarily be limited to:
  - Drawings of the pipes, fittings, joints, pipe specials and the assembly thereof.
  - ii. Pipe laying diagram and schedule showing location, length, design designation and designation by number of each pipe section and pipe special to be furnished and installed.
  - iii. All data on curve and bends for both horizontal and vertical alignment.

## 22.1.5 Quality Control

- A. Prior to dispatch of any product and/or material from source the Contractor shall notify the Engineer in writing in sufficient time to allow the Engineer the opportunity to inspect and test the product and/or material prior to delivery in accordance with Section 01400 of the specification.
- B. Products and materials shall be from a manufacturer/supplier who operates a quality control system which is registered to ISO 9000 series or approved equal.
- C. To allow the Engineer to inspect the Works the Contractor shall give the Engineer a minimum of 24 hours notice of carrying out the following activities on site:
  - Installation of pipeline.
  - ii. Hydrostatic testing of pipeline.
  - iii. Deflection measurement of pipeline.