Table 4-2 Live Load Element Factor, K_{LL}

Element	K_{LL}^{a}
Interior columns	4
Exterior columns without cantilever slabs	4
Edge columns with cantilever slabs	3
Corner columns with cantilever slabs Edge beams without cantilever slabs Interior beams	2 2 2
All other members not identified, including: Edge beams with cantilever slabs Cantilever beams One-way slabs Two-way slabs Members without provisions for continuous shear transfer normal to their span	1

^aIn lieu of the preceding values, K_{LL} is permitted to be calculated.