- D. Carefully scribe casework abutting other components, with maximum gaps of1 mm. Do not use additional overlay trim for this purpose.
- E. Secure cabinet and counter bases to floor using appropriate angles and anchorage.
- F. Countersink anchorage devices at exposed locations. Conceal with solid wood plugs of species to match surrounding wood; finish flush with surrounding surfaces.
- G. Site glaze glass materials using the Interior Dry method.
- H. Floor Duct Covers planks shall be battered together in sets of three with 100mm x 38mm notched Gujun or similar approved hardwood seating batten. Each set of three interconnected planks shall be fitted with two recessed aluminium ring type lifting handle.
- I. Frames to floor duct covers shall be provided along all edges and shall be 75mm x 50mm aluminium alloy angle complete with fishtail lugs at 450mm centres. Frames shall be cast in prepared openings in the concrete floor with the top of the frame set flush with the finished floor level. Aluminium alloy reversed 'T' angle cross braces shall be provided at suitable centres.

2.3.3 Adjusting

- A. Section 01700 Contract Close-out, 01400 Quality Control: Adjust installed work. Test installed work for rigidity and ability to support loads.
- B. Adjust moving or operating parts to function smoothly and correctly.

2.3.4 Cleaning

- A. Section 01700 Contract Close-out: Cleaning installed work.
- B. Clean casework, counters, shelves, hardware, fittings, and fixtures.

2.3.5 Schedules

Not Used.

END OF SECTION