Estidama construction submission at Certificate of Completion application

IDP-	R1: Integrated Development Strategy
	Narrative showing an updated process chart of the IDP highlighting changes from the design stage and listing successes and challenges during construction stage
	Updated implementation strategy
IDP-	R2: Tenant Fit-Out Design & Construction Guide
	Tenant Fit-Out Design and Construction Guide
IDP-	R3: Basic Commissioning
	List of all meetings attended by the Commissioning Agent through commissioning period and project handover, including dates
Final Commissioning Report, including:	
	Owner's Project Requirements
	Project commissioning specifications
	Verification of installation
	Operation & Maintenance Manual
NS-I	R2: Natural Systems Protection
	Evidence that features of ecological value have been protected during construction; for example, a construction management plan and dated photographs of successfully protected areas/features
	Updated development map delineating the built limits of all proposed development and disturbance, setback zones, and buffer areas
	Supporting calculations summarizing final total land area and protected areas
	Confirmation of the appointment of a management and maintenance organization (with a contract running for at least 5 years), if management not to be undertaken by the local municipality. The confirmation must contain details of individuals responsible and their duties in line with the strategy