E. At completion of the work, or at such times as the Engineer may direct, remove all temporary drainage installations and make good existing to the Engineer's satisfaction and as required by the concerned authorities.

17.1.12 Temporary Drainage

- A. The Contractor shall provide and maintain such temporary drainage installations, as may be necessary, in a manner approved by the Engineer and so as not to adversely affect adjacent areas and properties.
- B. Temporary drainage installations (storm water and foul water) may be connected to existing drains provided written permission is obtained from the Engineer, and provided such connection work is executed and maintained in strict accordance with the Engineer's directions.
- C. At completion of the work, or at such times as the Engineer may direct, remove all temporary drainage installations and make good existing to the Engineer's satisfaction and as required by the concerned authorities.

17.1.13 Temporary Fire Fighting Services

- A. The Contractor shall ensure and take all reasonable precautions to avoid out-breaks of fire on the works, temporary works, offices, stores and other places and things connected therewith.
- B. The Contractor shall safely store petroleum products, paints and other combustible, dangerous or hazardous goods. Comply with all rules regulations and orders made by any authorities having jurisdiction
- C. The Contractor shall provide and maintain in good order and hold available at all times, a sufficiency of efficient fire fighting facilities and equipment together with personnel trained in its use.
- D. The Contractor shall ensure all fire fighting facilities and equipment is as required and approved by the Civil Defence Authority.
- E. Fire fighting equipment shall always be fully operational and be tested routinely and approved by the Civil Defence Authority.
- F. The Contractor shall take adequate safety precautions during metal welding and torch cutting operations.
- G. Gasoline and other flammable liquids shall be stored in and dispensed from listed safety containers and in conformance with requirements of the Civil Defence.