- d. If stored outside, cover products to prevent UV degradation as recommended by the manufacturer.
- 4. The Contractor shall visually inspect all products upon delivery and report any damage to the Engineer.

1.1.7 Project Conditions

1.1.7.1 Environmental Limitations:

- Do not deliver or install interior finish carpentry until building is enclosed and weatherproof, wet-work in space is completed and nominally dry, and HVAC system is operating and will maintain temperature and relative humidity at occupancy levels through the remainder of construction period.
- Field Measurements: Where woodwork is indicated to be fitted to other construction, check actual dimensions of other construction by accurate field measurements before fabrication, and show recorded measurements on final shop drawings. Co-ordinate fabrication schedule with construction progress to avoid delaying the Work.
 - a. Verify locations of concealed framing, blocking, and reinforcements that support woodwork by accurate filed measurements before being enclosed. Record measurements on final shop drawings.

1.1.8 Co-Ordination

A. Co-ordinate sizes and locations of framing, blocking, reinforcements, and other related units of Work specified in other Sections to ensure that woodwork can be supported and installed as indicated.

1.1.9 Warranty

1.1.9.1 Special Warranty:

- 1. Written warranty executed by fabricator agreeing to repair or replace all architectural woodworks and applied finishes that fail in materials or finish within specified warranty period.
- Written warranty executed by installer agreeing to repair or replace all architectural woodwork, applied finishes, fixings (concealed and exposed) and associated metal works that fail in material, finish or workmanship within specified period.

A. Warranty Period:

1. Minimum 5 years from date of substantial completion.