E. The board shall be protected as work proceeds against prolonged exposure to sunlight, damage and displacement before finished surface protection is applied.

3.3.2.4 Precast Concrete Tiles

A. All joints shall be uniformly straight, in line and level.

3.3.3 Flood Testing

- A. The horizontal areas of waterproofing shall be tested prior to the installation of insulation.
- B. Testing shall be by flooding sections of the waterproofed area with a minimum 50mm head of water for 48 hours.
- C. Any area where leaks occur shall be drained, thoroughly dried, repaired and then re-tested.
- D. After completion of flood testing, remove all traces of water to the satisfaction of the Engineer.
- E. Installation of insulation board and concrete tiles shall not start until such time as the membrane is leak free and has been accepted by the Engineer.

END OF SECTION