## 1.3.12 Removal of Formwork

(Average air temperature approximately 25°C)

Table 1-1: Minimum Period Prior to Removal of Formwork

| Removal of formwork to:                        | Minimum<br>Removal | period | prior | to |
|--|--------------------|--------|-------|----|
| Slab and beam sides walls and unloaded columns | 1 Day              |        |       |    |
| Slab and beam soffits props left in position   | 7 Days             |        |       |    |
| Removal of props to slab and beam soffits      | 14 Days            |        |       |    |

**END OF SECTION**