



If IAQ test report demonstrates that maximum concentrations of contaminants have exceeded, additional flush-out procedures with outside air should be implemented. Test must be conducted again until it can be verified that contaminant levels does not exceed the acceptable range.

## **COMPLIANCE DOCUMENTATION**

Table 401.06(4): Documents Required

Project Stages	Submittal Documents
Design Permit Application	1. DM BLDG Al Sa'fat declaration.
Construction Completion Application	<ol> <li>Air testing company / laboratory trade license</li> <li>Air testing report. Report should include executive summary, test procedures, equipment list, test locations, test dates and result of each test &amp; calibration certificate for testing equipment &amp; calibration validity.</li> </ol>
After Completion	<ol> <li>Air testing company / laboratory trade license</li> <li>Air testing report after 6 months of usage. Report should include executive summary, test procedures, equipment list, test locations, test dates and result of each test &amp; calibration certificate for testing equipment &amp; calibration validity.</li> </ol>

## REFERENCES AND ADDITIONAL INFORMATION

Government of Dubai. (2003). Local Order No. 11 (law 53, 54 and 55) and Administrative Resolution (Law 61,62 and 63).

International Organization for Standardization. (2014). ISO 16000-01, Part 1: General aspects of sampling strategy.