2.1.8 Delivery, Storage, and Handling

- A. Deliver, store, protect and handle products to site under provisions of Section 01600.
- B. Do not change brands or sources of supply for masonry materials during the course of the work.
- C. Deliver unit masonry materials, other than bulk materials, to site in manufacturer's unopened containers, bundles, pallets or other standard packaging devices, fully identified with name, type, grade, colour and size.
- D. Protect all unit masonry material during shipment, storage and construction against wetting and soil age or intermixture with earth or other types of materials.
- E. Take all necessary precautions to prevent all masonry items from chipping, cracking or other damage during transportation, unloading and storage on site. Damaged units will not be allowed to be installed.
- F. Do not use metal reinforcing or ties having loose rust or other coatings that will reduce or destroy bond.
- G. Outside storage of masonry units and reinforcement shall be on plank platforms, off the ground, in dry locations.
- H. Inspect for damage.

2.1.9 Environmental Requirements

- A. Take all necessary precautions to keep mortar and blocks and other materials cool and in particular:
 - 1. Do not mix mortar or lay units while shade temperature is above 40°C, on a rising thermometer or above 43°C, or on a falling thermometer.
 - 2. Do not allow temperature of fresh mixed mortar to exceed 32°C. Take suitable measures to ensure this.
 - 3. Do not lay masonry units having a film of water on their surfaces.
 - 4. The Contractor will be deemed to have allowed in his Tender for all steps necessary for compliance with the above.

2.1.10 Coordination

- A. Coordinate work under provisions of Section 01039.
- B. Coordinate the masonry work with structural members veneer, installation of window anchors, ties and anchor bolts. etc.