

Fig. 502.02(1): Schematic For CO<sub>2</sub> based DCV System for Package Unit (Wall Mounted)




Fig. 502.02(2): Schematic For CO<sub>2</sub> based DCV System for Package Unit (Duct Mounted)

CO<sub>2</sub> sensors and related systems must be checked and re-calibrated as per manufacturer recommendations. Recalibration frequency must not exceed 12 months and must be carried out by specialised companies.