

906.02 SAFETY MEASURES

Standard barriers, barricades, signs, flashers and other protective measures will be provided for guiding, warning, and protecting vehicular and pedestrian traffic during construction.

All road closures and construction traffic shall be coordinated with local police and fire services.

906.03 TEMPORARY TRAFFIC SIGNALS

At locations of complex traffic movements, temporary and portable traffic signals will be used for the safe, orderly movement of traffic during construction.

906.04 MAINTENANCE OF TRAFFIC PLANS

A work phase plan shall be established by construction phases or sequence, indicating the duration of each phase or sequence. The plan shall include but not be limited to:

- maintenance of traffic circulation during construction,
- traffic control methods that need to be implemented,
- construction detours,
- Work areas per stage,
- temporary barrier locations and details,
- temporary signing and striping locations and details,
- temporary construction quantities.