- E. Promptly notify the Engineer and the Contractor of observed irregularities or non-conformance of work or products practices or materials at site, at the manufacturers or supplier's premises or during transportation...
- F. Perform additional tests as required by the Engineer.
- G. Attend preconstruction meetings and progress meetings as required.

15.1.7 Inspection Reports

- A. After each test, promptly Inspection Firms shall submit six copies of report to Contractor for transmittal to the Engineer.
- B. Inspection Reports shall include:
 - 1. Date issued.
 - 2. Project title and number.
 - 3. Name of inspector.
 - 4. Date and time of sampling or inspection.
 - 5. Identification of product and specifications section.
 - 6. Location in the Project.
 - 7. Type of inspection or test.
 - 8. Date of test.
 - 9. Record observations, analysis results and conclusions.
 - 10. Secure evidence or specimens along with photographs.
 - 11. Conformance with Contract Documents.
- C. When requested by the Engineer, interpretation of test results shall be provided.

15.1.8 Limits on Testing Authority

- A. The laboratory shall not release, revoke, alter, or enlarge the requirements of Contract Documents.
- B. The laboratory shall not approve any portion of the Work.
- C. The laboratory shall not assume any duties of the Contractor.
- D. The laboratory has no authority to stop the Work.