

5 EXPOSED AGGREGATE CONCRETE FINISHES (SECTION 03355)

5.1 Part 1 General

5.1.1 Related Documents

Section 01039-Coordination and Meetings

Section 01300-Submittals

Section 01400-Quality Control

Section 01600-Materials and equipment

Section 01700-Contract Close out

Section 03300-Cast-In Place Concrete

Section 03370-Concrete Curing

5.1.2 References

ACI 303R - Guide to Cast-in-Place Architectural Concrete.

5.1.3 Submittals for Review

- A. Section 01300 - Submittals.
- B. Samples: Submit two number 5 kg plastic buckets of each aggregate specified, illustrating size, colour and the extremes of colour range.

5.1.4 Quality Assurance

- A. Perform Work in accordance with section 03300 and ACI 303R.
- B. Maintain one copy of the document on site.

5.1.5 Mock-Up

- A. Section 01400 - Quality Control.
- B. Construct one horizontal field sample panel, 2m by 3m, with full aggregate colour range represented.
- C. Locate as directed by the Engineer.
- D. Mock-up may not remain as part of the permanent Work.

5.1.6 Pre-Installation Meeting

- A. Section 01039 - Coordination and Meetings.