## Estidama construction submission at Certificate of Completion application

	Copy of training material for security staff
For residential units provide in addition to the above, purchase receipts of weather-stripping and the following photographic evidence:	
	Weather-stripping installation and impermeable deck to deck partitioning installation
LBi-R3: Legionella Prevention	
	Operations & Maintenance Manual (OMM)
	Narrative and As-Built drawings of the air conditioning systems regardless of whether water-based cooling towers are present or not. The Narrative must explain the approach to Legionella Management and how it integrates into the OMM, or confirm no water-based systems are present
	Narrative and As-Built drawings of the project's other water-based systems. The Narrative must explain the approach to Legionella Management and how it integrates into the OMM
	Legionella Management Plan for the treatment of Legionella in the project's water-based systems
	All Audit checklists associated with the Legionella Management Process including but not limited to plant installation and commissioning, testing, training and competency and record keeping
PW-R1: Minimum Interior Water Use Reduction	
	Updated Building Water Calculator (if changed from design), confirming that the building's predicted interior potable water consumption is no greater than the baseline building interior potable water consumption using efficiency measures only Evidence that all purchased and installed covers have compliant outer surface SRIs
	Brief narrative describing all installed water conservation strategies
	Manufacturer information for all installed fixtures and fittings indicating flow rates and flow regulation systems
	Manufacturer information for all installed appliances including information on their water use
	Photographic evidence confirming installation of specified fixtures and appliances