

Summary of responsibility matrix for villa scenario:

| | Item description | Master Plan Developer | Building owner | Operators |
|----|---|-----------------------|----------------|-----------|
| 1 | Lead-in ducts including connection to manhole outside villa boundaries | ✓ | | |
| 2 | Manholes outside villa boundaries (including cover) | ✓ | | |
| 3 | Pull box inside the villa boundaries (including the cover) | | ✓ | |
| 4 | OSP fibre optic cables for single villa or complex villas connections (including supply, termination and testing) | | | ✓ |
| 5 | Supply and Installation of 4 core SM fibre Terminal Box | | ✓ | |
| 6 | Patch cords supply | | ✓ | |
| 7 | CP cabinet supply & installation (including accessories, power outlet and related elements) | | ✓ | |
| 8 | Supply and Installation of splitters inside the stand alone Meet-me-Room's racks | | | ✓ |
| 9 | Plot of 10 x 10 meter to be provided for each MMR | ✓ | | |
| 10 | Construction and Commissioning of Meet-Me- Room | ✓ | | |
| 11 | GAID & EID supply and placement in the villa unit | | ✓ | |