- a. Start of excavation for foundation (if necessary).
- b. Completion of reinforcement (if necessary).
- c. Start of installation of architectural woodwork.
- d. Start of installation of associated finishes (if necessary).
- e. Sampling and testing.

1.1.5.4 Testing Laboratory

- Testing of all materials shall be carried out by a suitably equipped site laboratory or in an independent laboratory as described in Section 01400 and approved by the Engineer.
 - a. Routine materials testing and site testing shall always be conducted in the site laboratory, unless otherwise agreed by the Engineer.
 - All sampling shall be witnessed by the Engineer, unless otherwise directed by the Engineer.
- During the course of the work, all required tests shall be carried out under the supervision of the Engineer, to ascertain the suitability of materials according to this specification.
- 3. The Contractor shall maintain a daily log of all tests carried out for the Engineer's review.

1.1.5.5 Mock-ups:

 Before fabricating and installing architectural woodwork, build mockups for each form of construction and finish required as directed by the Engineer to verify selections made under sample submittals and to demonstrate aesthetic effects and qualities of materials and execution.

A. Source Limitations:

 Engage a qualified woodworking firm to assume undivided responsibility for production and installation of interior architectural woodwork with sequence – matched wood veneers.

B. Quality Standard:

1. Unless otherwise indicated, comply with AWI's "Architectural Woodwork Quality Standards" for grades of interior architectural woodwork, construction, finishes, and other requirements. A. Provide AWI Quality Certification