

	Item description	Master Plan Developer	Building owner	Operators
11	fibre optic splitter supply and installation (from the approved lists of suppliers/vendors of both du and Etisalat)		✓	
12	Supply of fibre patch cords and Pre-patching the fiber patch cords between splitter's downlink ports to building fiber patch panels (ISP) and between splitter's uplink port to Outside plant fiber patch panels		✓	
13	Supply of Pigtail cords and splicing of Patch-Free splitter's downlink strands with the pigtail cords and terminating pigtails Cords in the fiber Patch Panels (ISP) , Splicing the Patch-Free splitter's Uplink strands with Feeder cable (For Etisalat)		✓	
14	CP cabinet supply & installation (including accessories including related elements)		✓	
15	Vertical and horizontal cable trays/pathways/Ducts/Micro Ducts supply & installation		✓	
16	Telecom rooms/spaces and related EM and civil requirements		✓	
17	Plot of 10 x 10 meter to be provided for each MMR	✓		
18	Construction of Meet-Me-Room	✓		
19	Commissioning of Meet-Me-Room			✓
20	fibre optic cables supply, pulling, termination and testing from the main telecom room to each mobile service room and roof-top room		✓	
21	fibre optic components for IBS-Connectivity (GSM): Supply and Installation of fibre optic pre-terminated patch panels, cross connect cabinets and fibre patch cords		✓	
22	GAID & EID supply and placement in the building unit		✓	